

NSRP RA Project 2019-483-011

Automated Detail Planning and Integrated Shipyard Operation with Engineering Data

ATI Project Manager: Nick Laney
Program Technical Representative: Dan Sfiligoi (NASSCO)

All Panel Meeting Feb 25, 2025

Project Team



Lead:

ShipConstructor Software USA

Patrick Roberts, VP of Sales & Operations

Rob Parker, Professional Services Manager

Darren Guillory, Technical Solutions Specialist



HII Ingalls Shipbuilding

Tim Warren, Manager



Fincantieri Marinette Marine

Rodney Klann, Methods Engineer



GD Bath Iron Works

Griffin Day, Planning





Floorganise

Ronald de Vries, Managing Director

Problem Statement

- Integrate all operational processes and information requirements with available engineering data and shipyard specific value streams to reduce costs and improve schedule adherence.




Project Objective

- Stand up a pilot program of Floor2Plan at each participating shipyard to research how to improve the shipyard efficiencies for higher levels of competitiveness (cost-price and lead-time) through digitization in engineering, organizational, and physical shipbuilding processes using an integrated Shipyard Manufacturing Execution System (MES) platform

Platform Roles


- PLM
 - PLM is the configured enterprise source of truth for the product model definition and the origin of the Model Based Enterprise (MBE), Part-Centric Digital Thread: **What will be manufactured, How it will be manufactured and tested, and What materials are needed** to manufacture it.
 - **PLM configuration controls the product model definition** through design iteration and change management, communicating the impact of change to downstream stakeholders.
- MES
 - **MES defines the detailed work activities and oversight of the execution of manufacturing work** (human and automated) to create a physical product, based on the configured product model definition.
 - **MES tracks work completion and what resources (materials, time/hours) have been consumed to complete the work.**

PLM/ERP/MES Roles in an integrated shipyard architecture




Model Based MBOM Workflows

- Model-based, part-centric architecture is required for effective integration




What is Floor2Plan?

 Used in RA project




↕
Data exchange
↕

Floor2plan



Methodology


ENGINEERING MODEL



We use the metadata from the drawings as input to drive automated templating




TEMPLATES



Floor2Plan then turns the engineering model metadata into a detailed planning



DETAIL PLANNING



More detail in operations planning fosters more control

COMPONENT



TASKS

Ta Mounting

522 : Welding

0%

Ta Mounting

521 : Grinding

0%

Co N01 (Sub Assembly) 22031

Link to ShipbuildingPLM 3D Model 37081.623

Component T...	Sub Assembly	Assembly	N01
		Block	321
		Workpackage	321 STRUCTURE ASSEMBLY

Ac Mounting: 8/16/2024 (33) - 11/27/2024 (48) 419789

Window Start	08/16/2024 (week 33)
Window Finish	11/27/2024 (week 48)
Planning Level	lvl4

PROGRESS

% 0%

Hours Budget	445
Hours Worked	0
Hours To Go	445
Progress	0%

Files

Related drawings ShipbuildingPLM

321-N01-C...

321-N01-...

321-N01-...

ALL FILES

Product Breakdown

- Stiffener (150)**
- Equipment (8)**
- Plate (155)**
- Assembly (34)**

Connect to MES Platforms



COMPONENT



TASKS

Ta Mounting 0%

522 : Welding

Ta Mounting 0%

521 : Grinding

Co N01 (Sub Assembly) 22031

Link to ShipbuildingPLM 3D Model 37081.623

Component T...	Sub Assembly	Assembly	N01
		Block	321
		Workpackage	321 STRUCTURE ASSEMBLY

Ac Mounting: 8/16/2024 (33) - 11/27/2024 (48) 419789

Window Start	08/16/2024 (week 33)
Window Finish	11/27/2024 (week 48)
Planning Level	lvl4

PROGRESS

% 0%

Hours Budget	445
Hours Worked	0
Hours To Go	445
Progress	0%

Files

Related drawings ShipbuildingPLM

Product Breakdown

- Stiffener (150)
- Equipment (8)
- Plate (155)
- Assembly (34)

Connect to MES Platforms



N01 x

N01 ☆

Edit

Model Views

Bill No ↓	MES State	SSI_View3D_Part2
		<ul style="list-style-type: none"> C2L02-C1 Outfit 321-BW-4 321-BW-3 321-BW-2 321-BW-1 321-OutfitP028P 321-OutfitP013S 321-OutfitS011P 321-OutfitS011P 321-OutfitS011S 321-OutfitS040P 321-OutfitS050P 321-OutfitS037S A299
B321N01_004	Start	
B321N01_003	Start	
B321N01_002	Start	
B321N01_001	Start	

Visualize MES State

Outfit x

Outfit ☆

Edit

BOM BOM Structure Production Documentation Files Where Used Changes

Parts ☆

Hidden

Name	Type	Revi...	Gene...	Total Wei...	MES St...	Bill No ↓
321-BW-4	Spool	A	2	36.819	Start	B321N01_004
321-BW-3	Spool	A	2	32.164	Start	B321N01_003
321-BW-2	Spool	A	3	195.921	Start	B321N01_002
321-BW-1	Spool	A	3	117.348	Start	B321N01_001
321-OutfitS011P	Stiffener	A	1	6.407		
321-OutfitS011S	Stiffener	A	1	6.407		
321-OutfitS040P	Stiffener	A	1	0.838		
321-OutfitS050P	Stiffener	A	1	0.819		
321-OutfitS037S	Stiffener	A	1	0.807		
321-BL-1	Spool	A	1	90.142		
321-BW-5	Spool	A	1	22.268		
321-BL-3	Spool					

Visualize MES State

Connect to MES Platforms

Floororganise
Triggering Smart Shipbuilding

Page: 1 of 1

Phase 1 Overview

- SSI and Floorganise conducted value stream mapping of information at each of the participating shipyards
- Captured business processes and data requirements of each participant
- Targeted groups at the shipyards included: Engineering, Production, IT, Planning and Project Control Processes
- Floorganise and SSI defined the data available to export from ShipbuildingPLM™ to the Floor2Plan Tool
- Floorganise and SSI held a workshop for project team members to demonstrate the workflow using SSI commercial ship data



Project Status

- Phase 1 activities completed
- Phase 2 in work
- Phase 2 plans:
 - Standing up pilot environments at HII and FMM
 - Requesting a 60 day no-cost extension due to delays in getting Phase 2 approval and setting up shipyard environments
 - Execute pilot program at each shipyard with ship data of their choice
 - Report findings of pilot programs at an industry workshop
 - May 13 – 15, 2025 SSI Offices, Mobile Alabama
 - Prepare and submit the final report

Project Benefits

- Understand relationships within operational processes prior to completion of the engineering model
- Use need by dates and actuals from production to determine priorities for the engineering team
- Automation of manual planning processes
- Direct progressing to support better project control

**>15% overall
hour savings per
project**

**35% reduction in
planning hours**

Questions?

