



# S2926: Improved Lead Bay Packing

## NSRP All Panel Meeting 2025

George Hinerman

Advanced Technology International

Connor McNulty-Ule

General Dynamic Electric Boat


February, 2025



# Agenda

1. Project Team
2. Platform/Issue Description
3. Objective
4. Technical Goals
5. Benefits/Pay Off
6. Project Schedule
7. Technical Approach
8. Technical Content and Status
9. Transition/Implementation Plan
10. Next Steps
11. Q & A


# Project Organizational Structure



# Project Overview/Objectives

- Issue Description:

- The current process for lead bay packing is time consuming and physically demanding. Lead is used as a fixed ballast to establish design equilibrium and stability, zero trim and zero list.
- Painted lead bricks ranging in weight from 0.5 to 56 lbs are delivered to the shop floor to transported using an overhead crane to the hull section. The bricks are then manually transported to the appropriate bin within the hull section.



- Project Objective(s):

- The objective of this effort is to develop a new process for delivering the lead bricks to the appropriate location on the hull section.
- Other objectives are to reduce the exposure to the lead and the repetitive physical strain on the employee





# Lead Ballast Installation (By the numbers)

Number of Handoffs

**77,000** times

Approximate Weight of Lead Packed (Platform 1)

**>100,000** lbs

Lead Brick Weight

**56** pounds

Approximate Weight of Lead Packed (Platform 2)

**>500,000** lbs

Average # of times handled (per brick)

**6-7** times

# of pieces installed


**>10,000** pieces




# Project Goals

**Goal 1:** Transportation Time

**Goal 2:** Time loading into hull



- fewer handoffs
- improved ergonomics




**89%**  
reduction in  
lifting time

Expected ROI: 5.57



# Project Schedule

- Recently Completed
  - ONR Period of Performance: 11 February 2022 through 31 December 2024



# Define Current/Future State


## Current stern loading process

1. Lead pallets next to module after delivery
2. Lead stand assembled next to module for loading. Forklift lifts lead pallet.
3. Pallet jack to transportation from lead to stand to access opening
4. **Lift table to lift lead parts into module. (12 ft, 150 lb max load)**
5. Lead packed into a bin. Shimmed and tight, blue marks indicate the parts have been counted.
6. Lead covers for installation.
7. Lead cover welded in place.


## Selected areas of improvement include:

1. Work Order Memorandum
2. Installing Rubber Liners
3. Submit Weight Count
4. **Stern loading lead transfer from pallet to access opening**
5. Vertical and Horizontal loading - trades pack bins

Current State



Future State





# Market Survey



LIFT TABLES



CONVEYORS




EXOSKELTONS



COBOTS

Increasing level of automation

# Execute Virtual Simulation Test Plan



Model-based design enabled efficient down-selection and iteration

# Vendor Down Selection

13 criteria were approved & scored






- Key Benefits:
  - Cycle time reductions
  - Flexible design
  - Lower costs
  - Substantial shorter lead times

**Recommendation: The Cooke Corporation**






Decision Matrix					
Criteria	Weighting	Baseline			
		Manual		Engineered Rigging	Cooke Corp.
		Score	Total	Total	Total
Reduction in Cycle Time	2.0	1.0	2.0	18.7	20.0
Reduction in Transportation	1.0	1.0	1.0	5.7	7.7
Feasibility of Success	3.0	10.0	30.0	20.0	24.0
Applicability to Other Loadings	1.0	10.0	10.0	6.0	9.0
Implementation Costs (1 - Expensive, 10 - Cheap)	1.5	10.0	15.0	2.0	11.5
Access Limitations (1 - Highly confined space, 10 - Low limitations)	1.0	10.0	10.0	3.7	5.7
Lead Quantity	1.0	1.0	1.0	9.7	6.7
Footprint - Amount of Space Occupied	1.0	9.0	9.0	9.7	8.0
Requires Process Change (1 - Drastic Change, 10 - No Change)	1.0	10.0	10.0	4.0	6.0
Ease of Operation	1.0	2.0	2.0	7.3	8.0
Safety Factors Considered	1.5	1.0	1.5	10.5	10.5
Off-the-shelf vs Customized Parts (10 - Off-the-shelf, 1 - Custom)	1	10.0	10.0	7.7	8.3
Lead Time	1.0	10.0	10.0	1.0	7.3
Total (Larger score is better)			111.5	105.8	132.7

# Iterative Design







# Risk Reduction - Prototype Safety Calculations




Dynamic calculations were reviewed to ensure safe operations in the shipyard

# Final Design



# Physical Demonstration Test



A physical mockup of the representative loading area was built to test and provide a training location





# Transition/Implementation

- Technology Transition Plan Status: Approved, (under annual review control)
- Transition Event: Successful completion of trial runs and formal acceptance of new process and training by safety and union representatives
- Stakeholder Implementation Commitment: None at this time.
  - Target: General Dynamics Electric Boat QP
- Opportunities to Leverage:
  - Handling of heavy equipment similar in size/weight
  - Transportation of other equipment and material for install





# Lessons Learned

- Human Subject Testing for exoskeletons
  - Navy Submarine Medical Research Laboratory (NSMRL) Internal Review Board (IRB) completed
- Iterative Design
  - Utilizing subject matter experts in design helped prevent challenges early
  - SMEs identified tight tolerances of hole opening would prevent challenges in using more complex, multi-conveyor solution
- Importance of Factory Acceptance Testing to mirror real-world application
  - Engaging end-users at Factory Acceptance Test at EBQP provided instant buy-in / training
  - Utilizing Lead Bricks during Factory Acceptance Test to verify systems lifting capability



# Questions?

